Capital Commerce Center Traffic Impact & Off-site Improvements


Town of Lancaster, MA

May 13, 2021





Estimating Traffic & Distribution



Institute of Transportation Engineers (ITE) – *Trip* Generation 10th Edition (2017)

- Professional Office
 - General Retail
- Multifamily Housing
 - Industrial Park



Estimating Traffic & Distribution



US Census Bureau Journey-to-Work & Journey-to-Home Data for Lancaster, MA

- Professional Office
- Multifamily Housing
 - Industrial Park

US Census Bureau Population Data vs. Competing Opportunities

Retail









Vehicle Trip Summary – All users

Time Period	EXISTING Vehicle Trips (Dunkin, Mobil, J.B. Hunt, FC Stars)	NET PROPOSED Vehicle Trips	Maynard Crossing Vehicle Trips
Weekday Daily	3,022	+ 8,220	10,258
Weekday AM Peak Hour	310	+ 1,008	430
Weekday PM Peak Hour	310	+ 1,022	930
Saturday Daily	3,494	+ 4,626	14,710
Saturday Midday Peak	330	+ 440	1,441

This is the SUM of all entering and exiting traffic in all directions



Trucks

Currently there are approximately 350 truck trips per day for J.B. Hunt + Central Mass Sand & Gravel



These trucks will be removed from the roadway network



MassDOT / Town Scheduled Transportation Improvements

Infrastructure Projects Below are Independent of the Capital Group Off-Site Infrastructure Improvement Program

- NEW Traffic Signal and Turn Lanes at Lunenburg Road / Main Street (Construction Spring/Summer 2022)
- NEW Traffic Signal and Turn Lanes at Main Street / Seven Bridge Road (Construction Spring/Summer 2022)
- NEW Ramp Realignment w/ Acceleration & Deceleration at Route 2 Interchange 34 (DESIGN – Construction Expected 2022-2025)
- NEW Ramp Realignment w/ Acceleration & Deceleration at Route 2 Interchange 35 & 36 (MassDOT Planning Stage)



Route 70 / 117 Signalization (MassDOT) - 2022






Route 70 / 117 Signalization (MassDOT) - 2022





Route 2 Exit 34 Reconstruction (MassDOT) – '22/'25 Currently Under Design by Jacobs Engineering





Route 2 Exit 35 Reconstruction (MassDOT) Currently in MassDOT Planning






Capital Group Off-Site Infrastructure Improvement Program

- NEW Traffic Signal and Turn Lanes at McGovern Boulevard / Lunenburg Road (Route 70)
- Interim Acceleration and Deceleration Lane Extension at Route 2 Exit 35 Westbound Ramps
- Interim Traffic Signal at Lunenburg Road (Route 70) / Fort Pond Road (Prior to MassDOT Future Interchange Reconstruction)
- Evaluation of Left-Turn Only for Site Trucks



Lunenburg Rd / McGovern Blvd (CGP) - 2022





Route 2 WB Exit 35 Off-Ramp (Interim)





Route 2 WB Exit 35 On-Ramp (Interim)





Lunenburg Road at Fort Pond Road (Interim)



- Construct interim traffic signal at intersection within same geometry.
- Interim traffic signal will be in place until MassDOT improvements at Exit 35 are completed.



Lunenburg Road at Old Union Turnpike Roundabout



Roundabout vs. Traffic Signal?

- Signal has <u>32</u> vehicle conflict points
- Roundabout has <u>8</u> vehicle conflict points

Space Constraints:

 Signal with turn lane storage requires more space away from intersection




Lunenburg Road at Old Union Turnpike Roundabout



- Designed for trucks to drive over the center brick inlay to navigate the roundabout.
- Traffic patterns in roundabout will significantly change with MassDOT Exit 34, 35 & 36 Projects.
- When designed, the roundabout design anticipated future development in the area.



Interstate 190 Ramp Discussion





Improvement Summary

MASSDOT & Town Transportation Improvements [Independent of the Capital Group Infrastructure Improvement Project]

- NEW Traffic Signal and Turn Lanes at Lunenburg Road / Main Street (Construction Spring/Summer 2022)
- NEW Traffic Signal and Turn Lanes at Main Street / Seven Bridge Road (Construction Spring/Summer 2022)
- NEW Ramp Realignment w/ Acceleration & Deceleration at Route 2 Interchange 34 (DESIGN Construction Expected 2022-2025)
- NEW Ramp Realignment w/ Acceleration & Deceleration at Route 2 Interchange 35 & 36 (MassDOT Planning Stage Expected to be Completed Before Full Build-Out)

Capital Grpup Off-Site Infrastructure Improvement Project

- NEW Traffic Signal and Turn Lanes at McGovern Boulevard / Lunenburg Road (Route 70)
- Interim Acceleration and Deceleration Lane Extension at Route 2 Exit 35 Westbound Ramps
- Interim Traffic Signal at Lunenburg Road (Route 70) / Fort Pond Road (Prior to MassDOT Future Interchange Reconstruction)
- Evaluation of Left-Turn Only for Site Trucks